

PROJECT ID: 11-03-026

Location: Key Largo, Florida

Completion Date: March 2012

Glass Square Footage: 325

Number of Panels: 27

Approximate Largest Panel Size:

Width: 1' 5"

Height: 10' 0"

Features:

1 All Wall System (3 Panels)

6 Split Wall Systems (4 Panels Each)

6' & 8' Track Lengths Respectively

AAMA 2603 White Frame Finish

LoE 366 Monolithic Laminated Glazing

Hurricane Impact Rated Application



PROJECT ID: 10-10-080

Location: Vero Beach, Florida

Completion Date: August 2011

Glass Square Footage: 463

Number of Panels: 39

Approximate Largest Panel Size:

Width: 2' 8"

Height: 7' 0"

Features:

9 Split Wall Systems (4 Panels Each)

1 All Wall System (2 Panels)

1 Single Door (Hinged Jamb) System (1 Panel)

3' to 10' Track Lengths

Single Door includes Panic Hardware

AAMA 2603 White Frame Finish

Grey Monolithic Laminated Glazing

Built in Accordance with Miami Dade



PROJECT ID: 07-07-008

Location: Myrtle Beach, South Carolina

Completion Date: August 2008

Location: Myrtle Beach, South Carolina

Completion Date: August 2008

Glass Square Footage: 434 (Doors Only)

Number of Panels: 28

Approximate Largest Panel Size:

Width: 2' 9"

Height: 7' 6"

Features

4 All Wall Systems (7 Panels Each)

20' Track Lengths

AAMA 2603 White Frame Finish

Solexia Green Insulated Laminated Glazing

Hurricane Impact Rated Application



PROJECT ID: 09-07-397

Location: Naples, Florida

Completion Date: March 2010

Glass Square Footage: 693

Number of Panels: 44

Approximate Largest Panel Size:

Width: 2' 9"

Height: 9' 6"

Features:

9 All Wall Systems

(4@2 Panels, 1@3 Panels, & 4@4 Panels)

3 Single Door Systems

(1@1 Panel, 1@3 Panels, & 1@9 Panels)

1 Split Wall System (4 Panels)

6' to 26' Track Lengths

135° No Post Application

Class I Clear Anodized Frame Finish

Hurricane Impact Rated Application



PROJECT ID: 08-09-220

Location: West Palm Beach, Florida

Completion Date: May 2009

Glass Square Footage: 180

Number of Panels: 9

Approximate Largest Panel Size:

Width: 3' 0"

Height: 8' 0"

Features:

1 Split Wall System

27 Track Length

Dark Bronze Anodized Frame Finish

Clear Monolithic Laminated Glazing

Hurricane Impact Rated Application



PROJECT ID: 07-05-028

Location: Ponte Vedra Beach, Florida

Completion Date: October 2007

Glass Square Footage: 133

Number of Panels: 12

Approximate Largest Panel Size:

Width: 2' 4"

Height: 8' 0"

Features:

3 Split Wall Systems (4 Panels Each)

8' to 10' Track Lengths

AAMA 2603 White Frame Finish

Grey Insulated Laminated Glazing

Hurricane Impact Rated Application



PROJECT ID: 12-10-082

Location: Tampa, Florida

Completion Date: August 2013

Glass Square Footage: 165

Number of Panels: 7

Approximate Largest Panel Size:

Width: 3' 0"

Height: 9' 0"

Features:

2 Single Door (Hinge Jamb) Systems

(1@3 Panels & 1@4 Panels)

9' & 12' Track Lengths Respectively

Two-tone Frame Finish

Southern Yellow Pine Veneer Interior

Natural Clay Exterior Frame Finish

LoE 366 Insulated Laminated Glazing

Hurricane Impact Rated Application



PROJECT ID: 07-01-002

Location: Ponte Vedra Beach, Florida

Completion Date: March 2008

Glass Square Footage: 143

Number of Panels: 6

Approximate Largest Panel Size:

Width: 3'

Height: 9'

Features:

1 Single Door (Hinge Jamb) System

20' Track Length

AAMA 2603 White Frame Finish

Grey Tinted Insulated Laminated Glazing

Hurricane Impact Rated Application

